39041.

01/10/99

Archaeoleg Cambria Archaeology

Tir Gofal Farm Visit Report Blaenwaun Ganol W/11/438

ACA Project Record No 39041 Report prepared for CCW by ACA

October, 1999

Archaeoleg Cambria Archaeology Shire Hall, 8, Carmarthen Street, Llandeilo, Carmarthenshire SA19 6AF Tel: (01558) 823121/823131

Fax: (01558) 823133 Email: cambria@acadat.com



W/11/438 Tir Gofal Application Number Blaenwaun Ganol, Llanwnnen, Lampeter, Address SN509488 NGR Ceredigion TG Project Officer Arfon Williams, Aberystwyth Archaeoleg Cambria Archaeology Project Record Number 39041 30/09/99 Visit Date

Visit Officer

Ken Murphy

TIR GOFAL SITE MANAGEMENT CATEGORY

As used in accompanying site gazetteer.

Category A - Sites and Monuments of National Importance

Category B - Sites and Monuments of Regional Importance

Category C - Sites/Features of Local Importance

Category D - Sites/Features needing further investigation (including damaged sites or sites with no defined physical presence).

TIR GOFAL COLOUR CODING

As used on accompanying holding maps.

Category A - Blue Scheduled Ancient Monuments

Grade 1 and 2* Listed Building

Red Other Sites and Monuments of National Importance

Other Buildings of National Importance

Red toning Registered Parks and Gardens of Historic Interest

Red Banding Registered Landscapes of Historic Interest

Category B - Amber Sites and Monuments of Regional Importance

Grade 2 Listed and Other Buildings of Regional Importance

Category C - Green Sites / Features of Local Importance

Buildings of Local Importance

Category D - Grey Sites / Features of Unknown Importance

ARCHAEOLOGICAL SITE STATUS

Terms used in gazetteer.

SAM.

Scheduled Ancient Monument. SAMs are notified under section 1 of the Planning (Listed Buildings and Conservation Areas) Act 1990. The register of SAMs is maintained and administered by Cadw.

LB1, LB2* & LB2.

Listed Building categories. Listed buildings are notified under section 1 of the Planning (Listed Buildings and Conservation Areas) Act 1990. The list is maintained and administered by Cadw.

HL - Landscapes of Exceptional and Great Historic Interest.

Defined by the Register of Landscapes, Parks and Gardens of Special Historic Interest in Wales: Part 2.1 Landscapes of Exceptional and Great Historic Interest The register is advisory only, and has no statutory powers. The register is being compiled by Cadw in partnership with the International Council on Monuments and Sites (ICOMOS) and is concerned with man-made, historic elements of the landscape.

HGP - Register of Historic Gardens & Parks.

Defined by the Register of Landscapes, Parks and Gardens of Special Historic Interest in Wales: Part 1 - Parks & Gardens. The register is advisory only, and has no statutory powers. The register is being compiled by Cadw in partnership with the International Council on Monuments and Sites (ICOMOS) and is concerned with man-made, historic elements of the landscape.

Tir Gofal Scheme			Tir Gofal Appl	ication No	W/11/420
Gazetteer of Archaeological Sit	es and Management Rec	commendations:	Blaenwaun Ganol,	Ceredigio	n
PRN 9458 Site name	BLAENWAUN GANOL			NGR	SN51004894
Site type GATE POST	Period	Post Med;Modern		Site Status	•
Description This stone stands approximately 1.6m prostrate and was noted as a possible it ever was anything other than a gate	Bronze Age standing stone.	There is nothing in	the size or shape of the	ne stone to st	s recorded uggest that
Recommendations There are no management recommend	ations.				
Management Category D		Visited by	KM	Visited On	30/09/99
PRN 18616 Site name	BLAENWAUN UCHAF			NGR	SN50624905
Site type QUARRY	Period	Post Med		Site Status	
Description A small, steep-sided quarry pit c. 10m	n by 10m and 4m deep in wo	odland.			
Recommendations There are no management recommend	ations for this site.				
Management Category D		Visited by	KM	Visited On	30/09/99
PRN 18620 Site name I	BLAENWAUN GANOL			NGR	SN50624854
Site type SAND PIT	Period	Post Med		Site Status	
Description This quarry in a corner of a field measure.	sures c. 30m by 30m and is 4	m deep, It lies unde	r pasture and scrub.		
Recommendations There are no management recommend	ations for this site.				
Management Category D		Visited by	KM	Visited On	30/09/99
PRN 39041 Site name I	BLAENWAUN GANOL			NGR	SN5148
Site type PROJECT RECORD	Period			Site Status	
Description					
Recommendations					
Management Category		Visited by	KM	Visited On	30/09/99

PRN 39042

Site name BLAENWAUN GANOL

NGR

SN5148

Site type FARM

Period

Post Med; Modern

Site Status

Description

The farm holding of Blaenwaun Ganol now includes the land and buildings of Blaenwaun Uchaf. Blaenwaun Ganol farmstead, PRN 39050) dates to the second half of the 19th century, but the site is clearly more ancient. The original Blaenwaun Uchaf farmstead (39043) lay 300m to the north of Blaenwaun Ganol farmstead and is equally ancient, but was removed to its present location (39055) in c. 1876. The land of the holding is totally enclosed, but nevertheless three distinct though overlapping zones of enclosure can be detected. To the east of Blaenwaun Ganol and old Blaenwaun Uchaf the land falls away gently onto poor quality rushy and boggy ground. The tithe map and early OS maps show that in the 19th century this was partially enclosed. Indeed, the enclosure pattern of this area is still weak and defined by low stony earth banks topped with straggling hedges and/or ditches. In some instances the hedges on the banks have completely gone and the area has reverted back to moorland. In a zone roughly from Blaenwaun Ganol and old Blaenwaun Uchaf farmsteads to the west up to the Llanwnen/Llanwenog parish boundary on gently sloping east-facing land the field system is old-established and consists of small irregular enclosures surrounded by earth banks topped with hedges. The land-use here is improved pasture and the boundaries are in fair to good condition with very little dereliction of hedges. Some hedges contain distinctive hedgerow trees particularly those that line the lane that runs east from Blaenwaun Uchaf farmstead. The third zone lies in Llanwenog parish on the highest point of the farm to the south of Blaencwrt. The enclosure pattern here though dating to at least 1840 has the appearance of being more recent than that to the east. Apart from roadside boundaries which are in good condition the low earth banks are now devoid of stock-proof hedges though two of them have lines of mature beech trees on them.

Recommendations

It is important that the field boundaries of what is probably the most ancient enclosed land - in the zone to the west of Blachwaun Ganol farmstead - are maintained in their current condition; this will require management and a little repair work where gaps have begun to open in some hedges. Elsewhere the less ancient enclosure pattern has began to break down; no maintainence or management of boundaries is required where this has occurred.

Management Categ	ory B		Visited by	KM	Visited On 30/09/99
PRN 39043	Site name	BLAENWAUN UCHAF	··· -··	-	NGR SN51954910
Site type FARMS	TEAD	Period	Post Med		Site Status

Description

This is the original site of Blaenwaun Uchaf farm prior to its relocation in about 1876. According to the owners of Blaenwaun Ganol the present Uchaf was built in 1876. This corresponds with the documentary evidence - the old farm is marked on the tithe map of 1844 but was deserted and the buildings gone by the OS survey of 1887. It is represented by a 'yard' defined by hedgebanks with a enclosure surrounded by hedgebanks to the west. The buildings consisted of two parallel ranges facing each other across the yard. These are now represented by low earthworks. It is uncertain which was the house and which the outbuildings. To the east of the buildings lies a pond (39044), to the southwest a gin (39045) and to the west a corm-drying kiln (39046)

Recommendations

It is unusual to discover a deserted farm in such good condition with most of its elements readily identifiable. Care should be taken not to disturb the remains of this site. It is particularly important that no earth-moving machinery is used on the site.

Management	Category B		Visited by	KM	Visited On	30/09/99
PRN 39044	Site name	BLAENWAUN UCHAF			NGR	SN51024912
Site type PO	ND	Period	Post Med		Site Status	

Description

This pond is now largely silted-up. It is approximately 20m by 20m square and is formed by a massive earth dam on its north, south and east sides. The dam is 4-5m wide and 3m high. Mature trees have rooted on the dam. It is unclear whether the dam was present in 1844 at the tithe survey - its was recorded in 1887 by the OS when Blaenwaun Uchaf farm had been abandoned.

Recommendations

This pond should be maintained in its current condition.

Management Category B Visited by KM Visited On 30/09/99

PRN 39045

Site name BLAENWAUN UCHAF

NGR

SN50964907

Site type GIN

Period

Post Med

Site Status

Description

This gin which lies in the old 'yard' of the deserted farm of Blaenwaun Uchaf is not marked on any maps. It lies on a slight slope which runs down from west to east and it is marked by a circular terrace/platform partly cut into and partly built out on the slope. The circle is approximate 8m diameter and stands to 0.5m high on the downslope side. A slight central boss presumably accommodated a central post/axle. The gin is now grass-covered, but the present owners of Blaenwaun Ganol remember a cobbled surface to the gin. The purpose of the gin is unknown.

Recommendations

This gin survives in relatively good condition, with little surface damage. It does, however, lie close to a field gate and care needs to be exercised to ensure that it is not subjected to damage from machinery or stock.

Management Category B Visited by KM Visited On 30/09/99

PRN 39046 Site name BLAENWAUN UCHAF NGR SN50944909

Site type CORN DRYING KILN? Period Post Med Site Status

Description

The owners of Blaenwaun Ganol farm state that the remains of a corn drying kiln may lie in a hedgebank to the west of old Blaenwaun Uchaf farm. The site is now very overgrown and nothing was seem during a site visit (Sept 1999). The field is known as Cae'r Odyn on the apportionment of the 1844 tithe map.

Recommendations

There are no management recommendations for this site.

Management Category D Visited by KM Visited On 30/09/99

PRN 39047 Site name BLAENWAUN UCHAF NGR SN511491

Site type CULTIVATION RIDGE Period Post Med Site Status

Description

Narrow ridge and furrow is visible in a small field of rough ground and marsh. The narrowness of the ridges, probably less than 1m, indicates hand cultivation - lazy beds - rather than ploughing. An old lane leads down to this ridge and furrow from Blachwaen Uchaf to the west. The small field in which these ridges lie was not created until after the tithe survey of 1844.

Recommendations

Maintain as existing.

Management Category C Visited by KM Visited On 30/09/99

PRN 39048 Site name BLAENWAUN GANOL NGR SN50984874

Site type QUARRY Period Post Med Site Status

Description

A small quarry pit, 15m by 5m now mostly infilled with rubbish.

Recommendations

There are no management recommendations for this site.

Management Category D Visited by KM Visited On 30/09/99

PRN 39049

Site name BLAENWAUN GANOL

NGR

SN50994893

Site type GATE POST

Period

Post Med

Site Status

Description

A rounded boulder c. 1.2m high, 1.2m wide and 1.2m thick has been used as a gate post. It is inscribed '1882' in neatly carved numbers.

Recommendations

Maintain as existing.

Management Category C

PRN 39050

Site name

BLAENWAUN GANOL

Site type

FARMSTEAD

Period

Post Med

Visited by KM

Visited On 30/09/99

NGR SN5093893

Site Status

Site Status

Site Status

Site Status

Site Status

Description

Blachwaun Ganol is an old established farmstead - it was certainly in existence by the early 19th-century. The location of the farm buildings are recorded on the 1844 tithe map but according to the present owners the farmhouse was rebuilt in c. 1860. It would seem that the outbuildings were constructed contemporaneously with or soon after this as a window sill on the old stable is dated: D J BUILT 1878. The stone-built outbuildings comprise a cowshed with attached pig stye, a cart house with stables? and the dated stables with a mill at the east end. The mill has been allocated number 39051. A 20th century brick-built cow shed has been attached to the stables and there is an assemblage of modern farm buildings at the farmstead. The stone-built farm buildings are in fair to good condition. The farmhouse has been modernised

Recommendations

Maintain as existing.

Management Cate	egory B		Visited by	KM	Visited On 30/09/99
PRN 29051	Site name	BLAENWAUN GANOL	'		NGR SN50954890
Site type CORN	MILL	Period	Post Med		Site Status

Description

This mill is integral to a stable block dated on a window sill: D J BUILT 1878. The mill now has no internal fittings. A metal overshot wheel is situated immediately to the east of the building. This was supplied by a concrete race (broken) from a mill pond that lay to the southwest (SN50934887). The pond is now filled in an covered with a modern concrete farm buildings. What seems to be a date stone with the number '56' carved on it has fallen into the wheel pit.

Recommendations

Maintain as existing.

Management Catego	у В		Visited by	KM	Visited On 30/09/99
PRN 39052	Site name	BLAENWAUN GANOL			NGR SN51004893
Site type POND		Period	Post Med		Site Status

Description

A pond, approximately 20m by 20m, retained by an earth and stone dam on the northern eastern and southern sides.

Recommendations

Maintain as existing.

Management Category C Visited by KM Visited On 30/09/99

PRN 39053

Site name BLAENWAUN GANOL

NGR

SN50834854

Site type QUARRY

Period

Post Med

Site Status

Description

A small quarry pit situated in scrub at the edge of a field. The quarry measures 10m by 5m and is 2m deep.

Recommendations

There are no recommendations for this site.

Management Category D Visited by KM Visited On 30/09/99

PRN 39054 Site name BLAENWAUN GANOL NGR SN50404864

Site type QUARRY Period Post Med Site Status

Description

A rounded shallow hollow approximately 30m by 20m in pasture may mark the site of an old quarry.

Recommendations

There are no management recommendations for this site.

Management Category D		Visited by	KM	Visited On 30/09/99
PRN 39055 Site name	BLAENWAUN UCHAF			<i>NGR</i> SN50654913
Site type FARMSTEAD	Period	Post Med		Site Status

Description

According to the current owners of Blaenwaun Ganol Farm, Blaenwaun Ucha farmstead was moved from its old site 300m to the east of Blaenwaun Ganol (PRN 39043) to its present location in 1876. The farmhouse and outbuildings probably date to 1876. The tithe map and 1891 OS map support this. The farmhouse is two-storeyed with a catslide roof to rear, 3-bayed rendered and recently modernised. A range of outbuildings lies to the north of the house. These are stone built with some red-brick detailing under a slate roof. Essentially it consists of one east-west aligned range with a barn at right angles at the east end. The main range is single-storey with a half loft over. At a later date, but judging from the OS map, pre 1891 a stable wing was added to the west end this was late extended by the addition of a cart house. The whole range contains many original fittings including cow stalls, windows and doors. However it has been disused for some time; slates are missing and there is general neglect.

Recommendations

This farmstead contains an interesting collection of farm buildings. These have not been modernised. It would be desirable to restore them, if a new role for them could be identified.

Management Categor	у В			Visited by	KM	Visited On	30/09/99
PRN 39056	Site name	CORN-BWT				NGR	SN50774937
Site type COTTAGE	:		Period	Post Med		Site Status	

Description

A cottage is marked here on the tithe map. It is named as Corn-pwt on the OS 1891 map but called Corn-bwt by the present owners of Blaenwaun Ganol. It is now abandoned, derelict and planted over with conifers. It was not possible to identify any remains at the time of survey (Sept 1999) though the owners of Blaenwaun Ganol state that some low walls survive.

Recommendations

Maintain as existing.

Management Category B Visited by KM Visited On 30/09/99

PRN 39057

Site name BLAENWAUN GANOL

NGR

SN51274876

Site type STANDING STONE?

Period Unknown

Site Status

Description

A stone is marked in this location of the 1964 OS 1:10 560 map. It is not marked on the tithe map or on earlier OS maps. It was not seem in a survey of 1999.

Recommendations

None:

Management Category

D

Visited by KM

Visited On 30/09/99

Tir Gofal Scheme Gazetteer of Archaeological Sites and Management Recommendation	Tir Gofal Application No W/11/438 ns: Blaenwaun Ganol, Ceredigion
Мар	
, 1844 Llanwnen parish tithe map,	
Ordnance Survey, 1891 XXIII.SW, 1:10 560 map	
Ordnance Survey, 1964 SN54NW,	



Gate post 9458.



General view of farm, 39042, showing beech trees on old hedgebank - zone three of the enclosure pattern.



39043, the original site of Blaenwaun Uchaf farmstead. The gin is the low earthwork in the centre of the photograph.




Blaenwaun Ganol farmhouse, 39050.




Blaenwaun Ganol farmstead, 39050, showing the carthouse and the mill, 39051.



Blaenwaun Ganol farmstead mill, 39051



Gate post, 39049.



Blaenwaun Uchaf, 39055, outbuildings.

TIR GOFAL APPLICATION: BLAENWAUN GANOL, CEREDIGION ACA Project Record No. 39041
Report prepared for CCW

Map scale 1:10,000

Reproduced from the 1999 1:10,000 Scale Digital Raster Map by permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office Crown Copyright Countryside Council for Wales Licence No. GD272825G

